



SHEET SIZE: 11X17
FERG MAP PAGE
487-A1
486-F1

UNDERGROUND DISTRIBUTION ENGINEERING				
WORK REQUEST NO		WORK REQUEST TITLE / ADDRESS		
40320506		10005 SCHOENTHAL RD		
PLANNED BY	PHONE	CELL PHONE	DATE PLANNED	NOTES
A. NAVARRO	446-4320	446-4320	1/28/2020	INSTALL 1950 FT OF 1-PH UG PRIMARY 1/0 CABLE
REVIEWED BY	PHONE	CELL PHONE	DATE REVIEWED	
M. ROBLES	353-3758			EACH DEMAND LOAD: 79 KVA EACH CONNECTED LOAD: 51.5 KVA
CUSTOMER CONTACT	PHONE	CELL PHONE	OH WR NO	
GRID NO	CIRCUIT NO	TOTAL LOAD	SCALE	PAGE
X- 2139743 Y-13793185	F041		NTS	1 OF 1

OUTAGES
NO OUTAGES REQUIRED.

ASSOCIATED WR#
40312644 - OH

LOCATES/PERMITS
DIG TESS #:1977025969
WATER: NONE
PERMIT#: NONE
HAND DIG#: YES
STAKING: NO
BRUSHCUT: NO
INACCESSIBLE LOCATION: NO

ENVIRONMENTAL NOTES

FIELD NOTES
SPARE CONDUIT TO BE INSTALLED FOR FUTURE LOOP FEED

MISCELLANEOUS NOTES
GATE CODE:
NOTIFY DESIGNER IF CHANGES ARE NEEDED.

IT IS ESSENTIAL THAT AN INSPECTION OF THE PROPOSED CPS ELEC. CONDUITS AND SLTL FOUNDATIONS BE MADE BY A CPS ENERGY INSPECTOR BEFORE AND AFTER THE POURING OF CONCRETE AND BACKFILL OF TRENCH. IF APPLICABLE, CALL FOR INSPECTION. TWENTY FOUR HOUR NOTICE IS REQUIRED. WHEN CALLING FOR AN INSPECTION. BE PREPARED TO REFERENCE WORK REQUEST NUMBER AND ADDRESS SHOWN ON THIS COPY. CALL BETWEEN 7:00 A.M. AND 2:30 P.M. MONDAY-FRIDAY, 353-3373

LEGEND

----- INSTALL 1/0AL XLPE 35KV PRIMARY CABLE

INSTALL JCT BOX

INSTALL RISER

CPS CABLE SCHEDULE				
FROM	TO	QTY	DESCRIPTION	
1	2	770'	INSTALL #1/0 AL XLPE 35KV CABLE	
2	3	590'	INSTALL #1/0 AL XLPE 35KV CABLE	
3	4	590'	INSTALL #1/0 AL XLPE 35KV CABLE	
TOTAL		1950'	INSTALL #2 AL XLPE 15KV CABLE	

